

Notes:

- 1. Ensure tree roots will not be damaged by spikes.
- 2. Alternative construction method use natural stone 225x100x100 min size, mortared on class ST2 concrete base. Base to extend 225 beneath bed level and extend 300 beyond end of pipe in invert of ditch.
- 3. All dimensions in millimeters.
- 4. Indicative layout and dimensions.



Standard Detail
Headwall Concrete Bagwork / Stonework

Version	Amendment		Date
Checked By:		Drawing Number:	Version:
B.Bartlett		CD 500 40	
Date Issued:		SD-500-18	_
Oct 16			